

Septic System Inspection

- 1) All septic systems to be installed shall be staked in place according to design plan approved by Board of Health, by a Registered Professional Engineer or Registered Professional Land Surveyor.
- 2) 24 hour notice will be required for all inspections.
- 3) The installer of the septic system shall be present at time of inspection, unless otherwise stated by the health agent. The installer will have on-site a copy of the approved plan.
- 4) Inspections are required for
 - A. Stone under tanks and/or pump chambers
 - B. When the system is excavated to the depth of bottom of stone. The sidewalls and bottom areas will be inspected prior to any stone or fill being placed.
 - C. When all fill, stone, pipes, D-box, tanks and any other components of proposed system are in place.
 1. covers on tank will be removed to inspect the inside.
 2. cover of D-box will be removed and water present to perform a flow test to assure proper draining of D-box.
- 5) Fill material: Company invoice showing date, delivery address, amount and type of fill (must state meets requirements for Title V septic sand) required from installer before issuance of Certificate of Compliance.
- 6) The system cannot be backfilled until a certified as-built has been approved by the Board of Health.
- 7) Failure to comply with any of the above will result in the building card not being signed.